



BAILEY BISHOP & LANE, INC.
 411 WEST BAYA AVENUE
 P. O. BOX 3717
 LAKE CITY, FL 32056-3717
 PH. (904) 752-5640
 FAX (904) 755-7771

CRYSTAL ACRES COLUMBIA COUNTY, FLORIDA

PLAT BOOK 6 PAGE 024
 SHEET 1 OF 1

FILE NUMBER 92-02977
 FILED AND RECORDED IN THE OFFICIAL RECORDS
 OF COLUMBIA COUNTY, FLORIDA
21 1992 AT 2:37 O'CLOCK P.
 RECORDED VERIFIED
P. H. Witt
 CLERK OF COURTS
 COLUMBIA COUNTY, FLORIDA
 BY: *M. Lane*



LOCATION MAP
 NOT TO SCALE

DESCRIPTION

THE SE 1/4 OF THE SE 1/4, SECTION 5, TOWNSHIP 5 SOUTH, RANGE 17 EAST, COLUMBIA COUNTY, FLORIDA LESS AND EXCEPT THE NORTH 1 ACRE AND LESS AND EXCEPT RIGHT-OF-WAY FOR JIM WITT ROAD, A COUNTY PAVED ROAD AND LESS AND EXCEPT RIGHT-OF-WAY FOR A COUNTY ROAD IN THE SOUTHWEST CORNER THEREOF, BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:
 COMMENCE AT THE SOUTHEAST CORNER OF SECTION 5, TOWNSHIP 5 SOUTH, RANGE 17 EAST, COLUMBIA COUNTY, FLORIDA AND RUN THENCE S 89°22'22" W ALONG THE SOUTH LINE OF SAID SECTION 5, 11.57 FEET TO THE WEST RIGHT-OF-WAY LINE OF JIM WITT ROAD AND TO THE POINT OF BEGINNING, THENCE CONTINUE S 89°22'22" W ALONG SAID SOUTH LINE, 1258.21 FEET THE EASTERLY RIGHT-OF-WAY LINE OF A COUNTY ROAD AND TO A POINT ON A CURVE, THENCE NORTHWESTERLY ALONG SAID EASTERLY RIGHT-OF-WAY LINE ALONG SAID CURVE CONCAVE TO THE SOUTHWEST AND HAVING A RADIUS OF 11,675.16 FEET ALONG A CHORD BEARING N 23°45'26" W, 147.62 FEET TO THE WEST LINE OF SAID SE 1/4 OF SE 1/4, THENCE N 00°00'38" E ALONG SAID WEST LINE, 1166.78 FEET TO A POINT THAT IS S 00°00'38" W AND 32.82 FEET FROM THE NORTHWEST CORNER OF SAID SE 1/4 OF SE 1/4, THENCE N 89°24'57" E PARALLEL TO THE NORTH LINE OF SAID SE 1/4 OF SE 1/4, 1311.61 FEET TO THE WEST RIGHT-OF-WAY LINE OF JIM WITT ROAD, THENCE S 00°32'19" E ALONG SAID WEST RIGHT-OF-WAY LINE, 232.56 FEET, THENCE S 00°38'49" E ALONG SAID WEST RIGHT-OF-WAY LINE, 850.64 FEET TO THE POINT OF TANGENCY OF A CURVE, THENCE SOUTHERLY ALONG SAID WEST RIGHT-OF-WAY LINE ALONG SAID CURVE CONCAVE TO THE WEST AND HAVING A RADIUS OF 2834.79 FEET ALONG A CHORD BEARING S 01°33'40" W, 218.44 FEET TO THE POINT OF BEGINNING. SAID LANDS BEING SUBJECT TO CLAY ELECTRIC COOPERATIVE TRANSMISSION LINE EASEMENT AND CLAY ELECTRIC COOPERATIVE POWER LINE EASEMENT. CONTAINING 39.31 ACRES, MORE OR LESS.

LEGEND

- NAIL SET IN PAVEMENT
- 3/4" IRON PIPE W/CAP
- 4"x4" CONC. MON. SET
- 4"x4" CONC. MON. FOUND
- ⊗ 3x3 METAL PLATE IN PAVEMENT
- PERMANENT REFERENCE MONUMENT (PRM) 4"x4" CONC. MON. (PLS 4303)

DEDICATION

KNOW ALL MEN BY THESE PRESENTS that D & W Land Trust 1 as owner has caused the lands hereon shown to be surveyed, subdivided and platted, to be known as CRYSTAL ACRES, and that all Rights-of-way and Easements are hereby dedicated to the perpetual use of the Public for uses as shown hereon.

OWNER:
Clinton F. Dicks
 Clinton F. Dicks, Trustee

Ron Taylor
 Witness

Guy Williams
 Guy Williams, Trustee

Red Taylor
 Witness

ACKNOWLEDGEMENT:

STATE OF FLORIDA, COUNTY OF COLUMBIA

The foregoing dedication was acknowledged before me this 17 day of September 1996, by Clinton F. Dicks, Jr., Trustee, D & W Land Trust 1. He is personally known to me or has produced _____ as identification and (did/did not) take an oath.

SIGNED: *Rana L. Davich*
 Notary Public
 My Commission Expires: _____

ACKNOWLEDGEMENT:

STATE OF FLORIDA, COUNTY OF COLUMBIA

The foregoing dedication was acknowledged before me this 17 day of September 1996, by Guy Williams, Trustee, D & W Land Trust 1. He is personally known to me or has produced _____ as identification and (did/did not) take an oath.

SIGNED: *Rana L. Davich*
 Notary Public
 My Commission Expires: _____

ACCEPTANCE FOR MAINTENANCE

I HEREBY CERTIFY THAT THE IMPROVEMENTS HAVE BEEN CONSTRUCTED IN AN ACCEPTABLE MANNER AND IN ACCORDANCE WITH COUNTY SPECIFICATIONS OR THAT A PERFORMANCE BOND OR INSTRUMENT IN THE AMOUNT OF \$ _____ HAS BEEN POSTED TO ASSURE COMPLETION OF ALL REQUIRED IMPROVEMENTS AND MAINTENANCE IN CASE OF DEFAULT.

SIGNED: *Jerry Duda* DATE: 9-30-96
 Director of Public Works

COUNTY ATTORNEY'S CERTIFICATE

I HEREBY CERTIFY THAT I HAVE EXAMINED THE FORGOING PLAT AND THAT IT COMPLIES WITH THE COLUMBIA COUNTY SUBDIVISION ORDINANCE AND CHAPTER 177 OF THE FLORIDA STATUTES.

SIGNED: _____ DATE: _____
 County Attorney, Columbia Co.

COMMISSION APPROVAL

SIGNED: *John M. Lane*
 Chairman

DATE: 10-3-96

ATTEST: *P. H. Witt*
 Clerk

CLERK'S CERTIFICATE



This plat having been approved by the Columbia County Board of County Commissioners is accepted for files and recorded this 7 day of March, 1996, in Plat Book 6, Pages 174 and P. H. Witt

SIGNED: _____
 Clerk of Circuit Court

SURVEYOR'S CERTIFICATE

I HEREBY CERTIFY THAT THIS PLAT IS A TRUE AND CORRECT REPRESENTATION OF THE LANDS SURVEYED AND SHOWN HEREON, THAT THE SURVEY WAS MADE UNDER MY RESPONSIBLE DIRECTION AND SUPERVISION, THAT PERMANENT REFERENCE MONUMENTS AND PERMANENT CONTROL POINTS HAVE BEEN PLACED AS SHOWN AND THAT THE SURVEY DATA SHOWN HEREON COMPLIES WITH ALL OF THE REQUIREMENTS OF THE COLUMBIA COUNTY SUBDIVISION ORDINANCE NO. 78-7 AND CHAPTER 177, FLORIDA STATUTES.

DATE 9-12-96 SIGNED *John M. Lane*
 JOHN M. LANE, LAND SURVEYOR 4303



NOTES:

1. BEARINGS PROJECTED FROM THE CENTERLINE OF JIM WITT ROAD.
2. TOTAL ACRES IN SUBDIVISION IS 39.31 ACRES.
3. SUBDIVISION CONSISTS OF 6 LOTS RANGING IN SIZE FROM 5.001 TO 10.01 ACRES.
4. PROPERTY IS ZONED A-1.
5. ACCORDING TO THE FLOOD INSURANCE RATE MAP (COMMUNITY PANEL NO. 120070 0175 B, EFFECTIVE DATE JANUARY 6, 1988) THE ABOVE DESCRIBED LANDS LIE IN ZONE X, AN AREA DETERMINED TO BE OUTSIDE THE 500-YEAR FLOODPLAIN.
6. PRELIMINARY PLAT APPROVED ON AUGUST 15, 1996.

SPECIAL NOTES

NOTICE: ALL UTILITY EASEMENTS SHOWN ON THIS PLAT SHALL BE EASEMENTS FOR THE CONSTRUCTION, INSTALLATION, MAINTENANCE AND OPERATION OF ELECTRIC, TELEPHONE, GAS, CABLE TELEVISION SERVICES AND ANY OTHER PUBLIC UTILITIES.

NOTICE: THERE MAY BE ADDITIONAL RESTRICTIONS THAT ARE NOT RECORDED ON THIS PLAT THAT MAY BE FOUND IN THE PUBLIC RECORDS OF THIS COUNTY.

OFFICIAL RECORDS
 BOOK 2228 PAGE 2428